

Addendum # 2 Request for Information Questions and Answer

Bid Closing: **August 29th, 2019** at **2:00PM** (Local Time)

Page 1 of 2

Bid Number: **FPDC-140970MAW**

Date: **August 21, 2019**

BID MUST BE SUBMITTED ON OR ATTACHED TO THIS SIGNED FORM

RETURN BIDS AS SHOWN BELOW

Copies of bid, descriptive literature or supplemental materials required:

Seven 7 (Number) Copies

U.S. Mail /Hand Delivery/Express Mail/Courier Service
Address: (Including Federal Express, UPS, etc.)

The University of Texas MD Anderson Cancer Center
Fanning Holcombe Building
6900 Fannin Street Suite 09.1085
Houston, Texas 77030
Attn: Mariam Walker

BIDS MUST BE SUBMITTED IN A SEALED ENVELOPE IDENTIFIED BY THE COMPANY NAME. BID NUMBER MUST BE SHOWN ON THE LOWER LEFT HAND CORNER OF THE ENVELOPE.

BIDS MAY BE SUBMITTED AT ANY TIME UNTIL BID CLOSING DATE.

THE UNIVERSITY OF TEXAS MD ANDERSON CANCER CENTER RESERVES THE RIGHT TO REJECT ANY AND ALL BIDS OR ANY PART THEREOF.

BIDDER MUST COMPLETE AND SIGN BELOW

Company Name: _____

Mailing Address: _____
(STREET OR BOX #)

(CITY) (STATE) (ZIP)

Telephone No.: _____ / _____
AC

Email Address: _____

(Authorized Signature) (DATE)

(Typed or Printed Name and Title)

GENERAL

Addendum # 2 is generated to add the following:

1. RFI, Questions and Answers.

DIRECT QUESTIONS TO:

Mariam Walker: mwalker2@mdanderson.org

RFI QUESTIONS AND ANSWERS

Plan Development for Zebrafish Expansion in CRB-B
Project No. 140970
RFP No. FPDC-140970MAW

RFP Addendum # 2, August 21, 2019

RFI No. 1 – 8 Questions

Question 1: How thick is the concrete that requires saw cutting?

Answer 1: It is expected that slab depth is between 5" and 6".

Question 2: Will MD Anderson GPR and map the floors or is it the contractor's responsibility?

Answer 2: GC to include scope for any required existing conditions investigation within or below the slab.

Question 3: Is there an ICRA plan for exhausting during construction? Can we double scrub the air and vent into the hallway?

Answer 3: The contractor is responsible for providing an ICRA plan; prior to preconstruction meeting a "Temporary Containment" plan shall be submitted in Project Workspace for review and approval. The TC plan shall satisfy all requirements listed in IAQ. This project is under Class III Precautions,

- 1) A construction ante-room is required;
- 2) Construction area shall maintain negative air pressure;
- 3) HEPA filter is required.

The TC plan shall specify how the ante-room and temporary containment will be constructed.

Question 4: Will MEP work in corridors be performed after-normal hours?

Answer 4: MEP in corridor will be after hours/weekend.

Question 5: Please advise if contractor is to carry data scope?

Answer 5: Contractor does not carry Data. Owner will subcontract.

Question 6: Will saw-cut scope require floor X-ray?

Answer 6: GC to include floor x-ray

Question 7: Please provide detail for structural platform note 12 on sheet P10-10.

Answer 7: Platform to be designed per 05 53 13.

Question 8: Please provide Finish Schedule.

Answer 8: All finishes are provided on the drawings. See sheet A12-00.